

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Ute Tribal 10-15-4-1W				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT UNDESIGNATED				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) 2OG0005609			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Gerald N. Andersen						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 657 W Lakeview Rd., Lindon, UT 84042						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') Ute Tribe			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL	FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN			
LOCATION AT SURFACE	1797 FSL 2162 FEL		NWSE	15	4.0 S	1.0 W	U			
Top of Uppermost Producing Zone	1797 FSL 2162 FEL		NWSE	15	4.0 S	1.0 W	U			
At Total Depth	1797 FSL 2162 FEL		NWSE	15	4.0 S	1.0 W	U			
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 1797			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1168			26. PROPOSED DEPTH MD: 7270 TVD: 7270				
27. ELEVATION - GROUND LEVEL 5035			28. BOND NUMBER RLB0010462			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	12.25	8.625	0 - 300	24.0	J-55 ST&C	8.3	Class G	138	1.17	15.8
PROD	7.875	5.5	0 - 7270	15.5	J-55 LT&C	8.3	Premium Lite High Strength	364	3.26	11.0
							50/50 Poz	363	1.24	14.3
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Mandie Crozier				TITLE Regulatory Tech			PHONE 435 646-4825			
SIGNATURE				DATE 10/10/2011			EMAIL mcrozier@newfield.com			
API NUMBER ASSIGNED 43013510030000				APPROVAL Permit Manager						

NEWFIELD PRODUCTION COMPANY
 UTE TRIBAL 10-15-4-1W
 NW/SE SECTION 15, T4S, R1W
 DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0' – 2,095'
Green River	2,095'
Wasatch	6,995'
Proposed TD	7,270'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 2,095' – 6,995'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM**

a. Casing Design: Ute Tribal 10-15-4-1W

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	300'	24.0	J-55	STC	2,950 17.53	1,370 14.35	244,000 33.89
Prod casing 5-1/2"	0'	7,270	15.5	J-55	LTC	4,810 2.08	4,040 1.75	217,000 1.93

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: Ute Tribal 10-15-4-1W

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	300'	Class G w/ 2% CaCl	138 161	30%	15.8	1.17
Prod casing Lead	5,270'	Prem Lite II w/ 10% gel + 3% KCl	364 1187	30%	11.0	3.26
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363 451	30%	14.3	1.24

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:
The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a **2M** system, and individual components shall be operable as designed. Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 300 feet will be drilled with an air/mist system. The air rig is equipped with a 6 1/2" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ± 300 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated

bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.


10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the first quarter of 2012, and take approximately seven (7) days from spud to rig release.

CONFIDENTIAL

T4S, R1W, U.S.B.&M.**NEWFIELD EXPLORATION COMPANY**

WELL LOCATION, 10-15-4-1W, LOCATED
AS SHOWN IN THE NW 1/4 SE 1/4 OF
SECTION 15, T4S, R1W, U.S.B.&M.
DUCHESNE COUNTY, UTAH.


**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.

WELL LOCATION:
10-15-4-1W

ELEV. UNGRADED GROUND = 5035.2'


THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST
OF MY KNOWLEDGE AND BELIEF.

**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 10-10-10	SURVEYED BY: S.V.	VERSION:
DATE DRAWN: 10-18-10	DRAWN BY: F.T.M.	V1
REVISED: 06-05-12 F.T.M.	SCALE: 1" = 1000'	

10-15-4-1W
(Surface Location) NAD 83
LATITUDE = 40° 07' 57.79"
LONGITUDE = 109° 58' 50.96"




◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on
an N.G.S. OPUS Correction. LOCATION:
LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'

RECEIVED: October 10, 2011

Access Road Map



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

10-15-4-1W

SEC. 15, T4S, R1W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY: C.H.M. REVISED: 06-05-12 D.C.R. VERSION:

DATE: 10-26-2010

SCALE: 1:100,000


V1

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



Legend

- Existing Road
- Proposed Road
- Previously Proposed Road

Total Road Distances

Proposed Road ± 1,531'

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY


10-15-4-1W
SEC. 15, T4S, R1W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	C.H.M.	REVISED:	06-05-12 D.C.R.	VERSION:
DATE:	10-26-2010			V1
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET

B

Proposed Pipeline Map

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

10-15-4-1W
SEC. 15, T4S, R1W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY: C.H.M. REVISED: 06-05-12 D.C.R. VERSION:
DATE: 10-26-2010
SCALE: 1" = 2,000'

V1**TOPOGRAPHIC MAP**

SHEET

C

Exhibit "B" Map**Proposed Location
10-15-4-1W****Legend**

1 Mile Radius



Proposed Location

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

**10-15-4-1W
SEC. 15, T4S, R1W, U.S.B.&M.
Duchesne County, UT.**

DRAWN BY: C.H.M. REVISED: 06-05-12 D.C.R. VERSION:

DATE: 10-26-2010

SCALE: 1" = 2,000'

V1**TOPOGRAPHIC MAP**

SHEET

D

**NEWFIELD PRODUCTION COMPANY
UTE TRIBAL 10-15-4-1W
NW/SE SECTION 15, T4S, R1W
DUCHESNE COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site Ute Tribal 10-15-4-1W located in the NW 1/4 SE 1/4 Section 15, T4S, R1W, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed in a southwesterly direction approximately 2.3 miles to it's junction with an existing road to the east; proceed in an easterly and then southerly direction approximately 4.5 miles to it's junction with an existing road to the east; proceed in a southeasterly direction approximately 2.9 miles to it's junction with an existing road to the northeast; proceed northeasterly approximately 0.9 miles to it's junction with an existing road to the east; proceed easterly approximately 0.2 miles to it's junction with an existing road to the northeast; proceed northeasterly - 2,328' \pm to ti's junction with the beginning of the proposed access road to the northeast; proceed northeasterly along the proposed access road approximately 1,531' \pm to the proposed well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

Approximately 1,531' of access road is proposed for the proposed well. See attached **Topographic Map "B"**.

The proposed access road will be an 20' crown road (10' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. **LOCATION OF EXISTING WELLS**

Refer to Exhibit "B".

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District
Water Right : 43-10136

Maurice Harvey Pond
Water Right: 47-1358

Neil Moon Pond
Water Right: 43-11787

Newfield Collector Well
Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the

reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

- b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP – Gerald N. Andersen.

12. OTHER ADDITIONAL INFORMATION

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. State of Utah Antiquities Project Permit #U-10-MQ-0846p 12/21/10, prepared by Montgomery Archaeological Consultants. A revised Arch report will be forthcoming. Paleontological Resource Survey prepared by, SWCA Environmental Consultants, 12/3/10. See attached report cover pages, Exhibit "D".

Newfield Production Company requests 1,531' of planned access road be granted. **Refer to Topographic Map "B"**. Newfield Production Company requests 1,431' of surface gas line be granted. Newfield Production Company requests 1,464' of buried water line be granted.

It is proposed that the disturbed area will be 60' wide to allow for construction of the proposed access road, a 10" or smaller gas gathering line, a 4" poly fuel gas line, a buried 10" steel water injection line, a buried 3" poly water return line, and a and a 14" surface flow line. The planned access road will consist of a 20' permanent running surface (10' either side of the centerline) crowned and ditched in order to handle any run-off from any precipitation events that are prevalent to this area. The maximum grade will be less than 8%. There will be no culverts required along this access road. There will be turnouts as needed along this road to allow for increases in potential traffic issues. There are no fences encountered along this proposed road. There will be no new gates or cattle guards required. All construction material for this access road will be borrowed material accumulated during construction of the access road.

Both the proposed surface gas and buried water lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** The proposed water pipelines will be buried in a 4-5' deep trench constructed with a trencher or backhoe for the length of the proposal. The equipment will run on the surface and not be flat bladed to minimize surface impacts to precious topsoil in these High Desert environments. If possible, all proposed surface gas pipelines will be installed on the same side of the road as existing gas lines. The construction phase of the planned access road, proposed gas lines and proposed water lines will last approximately (5) days.

In the event that the proposed well is converted to a water injection well, a Sundry Notice 3160-5 form will be applied for through the Bureau of Land Management field office.

For a ROW plan of development, please refer to the Greater Monument Butte Green River Development SOP and as well as the Castle Peak and Eight Mile Flat Reclamation and Weed Management Plan.

Surface Flow Line

Newfield requests 1,397' of surface flow line be granted. The Surface Flow Line will consist of up to a 14" bundled pipe consisting of 2-2" poly glycol lines and 1-3" production line. For all new wells, Newfield. **Refer to Topographic Map "C"** for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures:

Clearing and Grading: No clearing or grading of the ROW will be required. The centerline of the proposed route will be staked prior to installation. Flow lines shall be placed as close to existing roads as possible without interfering with normal road travel or road maintenance activities. Due to the proximity of existing facilities, no temporary use or construction/storage areas are anticipated. If necessary, temporary use or construction/storage areas will be identified on a topographic map included in the approved permit.

Installation: The proposed flow lines will be installed 4-6" above the ground. For portions along existing two-track and primary access roads, lengths of pipe will be strung out in the borrow ditch,

welded together, and rolled or dragged into place with heavy equipment. For pipelines that are installed cross-country (not along existing or proposed roads), travel along the lines will be infrequent and for maintenance needs only. No installation activities will be performed during periods when the soil is too wet to adequately support installation equipment. If such equipment creates ruts in excess of three (3) inches deep, the soil will be deemed too wet to adequately support the equipment.

Termination and Final Reclamation: After abandonment of the associated production facilities, the flow lines will be cut and removed, and any incidental surface disturbance reclaimed. Reclamation procedures will follow those outlined in the Castle Peak and Eight Mile Flat Reclamation and Weed Management Plan.

- a) Newfield Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Newfield is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the Ute Tribal 10-15-4-1W, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Ute Tribal 10-15-4-1W, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office as well as the Ute Tribe Energy and Mineral Department shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Name: Corie Miller

Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052

Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #10-15-4-1W, NW/SE Section 15, T4S, R1W, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage for this well is covered by the Bureau of Indian Affairs Bond #RLB0010462.


I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


9/7/12

Date

Mandie Crozier
Regulatory Analyst
Newfield Production Company

Typical 2M BOP stack configuration







NEWFIELD EXPLORATION COMPANY**LOCATION LAYOUT****10-15-4-1W****Pad Location: NWSE Section 15, T4S, R1W, U.S.B.&M.****NOTE:**

The topsoil & excess material areas are calculated as being mounds containing 2,030 cubic yards of dirt (a 10% fluff factor is included). The mound areas are calculated with push slopes of 1.5:1 & fall slopes of 1.5:1.


SURVEYED BY: S.V.	DATE SURVEYED: 10-10-10	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 10-18-10	V1
SCALE: 1" = 50'	REVISED: F.T.M. 06-05-12	

Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: October 10, 2011

NEWFIELD EXPLORATION COMPANY**CROSS SECTIONS****10-15-4-1W***Pad Location: NWSE Section 15, T4S, R1W, U.S.B.&M.*

NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1

**Typical Diversion Drainage****Cross Section Detail**

NOT TO SCALE


ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	2,130	2,130	Topsoil is not included in Pad Cut	0
PIT	690	0		690
TOTALS	2,820	2,130	1,160	690

SURVEYED BY: S.V.	DATE SURVEYED: 10-10-10	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 10-18-10	V1
SCALE: 1" = 50'	REVISED: F.T.M. 06-05-12	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: October 10, 2011

NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****10-15-4-1W***Pad Location: NWSE Section 15, T4S, R1W, U.S.B.&M.*

SURVEYED BY: S.V.	DATE SURVEYED: 10-10-10	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 10-18-10	V1
SCALE: 1" = 50'	REVISED: F.T.M. 06-05-12	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: October 10, 2011

MEMORANDUM
of
EASEMENT, RIGHT-OF-WAY
and
SURFACE USE AGREEMENT

This Easement, Right-of-Way and Surface Use Agreement ("Agreement") is entered into this 9th day of Nov., 2011 by and between **Gerald N. Andersen Family Trust, Gerald N. Andersen and Rhea J. Andersen** whose address is 657 W. Lakeview Road, Lindon, Utah 84042, ("Surface Owner," whether one or more) and Newfield Production Company, a Texas corporation ("NEWFIELD"), with offices at 1001 Seventeenth Street, Suite 2000, Denver, Colorado 80202, covering certain lands, (the "Lands") situated in Duchesne County, Utah described as follows:

Township 4 South, Range 1 West

Section 15: SE1/4 NW1/4; SW1/4 NE1/4; W1/2 SE1/4; E1/2 SW1/4; SW1/4 SW1/4.

Section 16: SE1/4 SE1/4; S1/2 SW1/4 SE1/4

Duchesne County, Utah
Being 340 acres, more or less

For and in consideration of the sum of ten dollars (\$10.00), and other valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the undersigned hereby agree to the terms and provisions set forth as follows:

1. Compensation for Well; Release of All Claims

NEWFIELD shall pay to Surface Owner the sum as set forth in and according to the terms of that certain Letter Agreement for Easement, Right of Way and Surface Use by and between Surface Owner and NEWFIELD, dated Nov. 9th, 2011 as full payment and satisfaction for any and all detriment, depreciation, injury or damage of any nature to the Lands or growing crops thereon that may occur as a result of NEWFIELD's drilling or completion operations or its continuing activities for the production or transportation of oil, gas, or other hydrocarbons or products associated with the foregoing including, but not limited to, surface use, access, pipelines, gathering lines, pipeline interconnections, and any and all other reasonable or customary uses of land related to said operations or activities.

2. Grant of Right of Way and Easement

Surface Owner hereby grants, bargains, leases, assigns, and conveys to NEWFIELD an easement and right-of-way for the purpose of construction, using and maintaining access roads, locations for surface equipment and subsurface gathering lines for each well drilled upon the Lands, pipelines, and pipeline interconnections for two years from date of this agreement and so long thereafter as NEWFIELD's oil and gas leases remain in effect.

This Agreement shall be binding upon the respective heirs, executors, administrators, successors, and assigns of the undersigned. This agreement replaces and supersedes any and all prior agreements covering the lands described herein.

These Parties hereto have executed this document effective as of the day first above written.

SURFACE OWNER

NEWFIELD PRODUCTION COMPANY

By: 

Gerald N. Andersen, Trustee

By: _____

By: 

Rhea J. Andersen, Trustee

STATE OF UTAH)
)ss
COUNTY OF UTA #)



This instrument was acknowledged before me this 07th day of Nov., 2011 by
Gerald N. Andersen Family Trust, Gerald N. Andersen and Rhea J. Andersen, Private Surface Owners.

Witness my hand and official seal.


Notary Public

My commission expires 11-10-14

STATE OF COLORADO)
)ss
COUNTY OF DENVER)

This instrument was acknowledged before me this _____ day of _____, 2011 by
_____, as _____ of Newfield Production Company,
a Texas corporation, on behalf of the corporation.

Witness my hand and official seal.



Notary Public

My commission expires _____

CONFIDENTIAL



Map Produced by Diana Mason



ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name Ute Tribal 10-15-4-1W
API Number 43013510030000 **APD No** 4765 **Field/Unit** UNDESIGNATED
Location: 1/4,1/4 NWSE **Sec** 15 **Tw** 4.0S **Rng** 1.0W 1797 FSL 2162 FEL
GPS Coord (UTM) **Surface Owner** Gerald N. Andersen

Participants

M. Jones (UDOGM), T. Eaton (Newfield), Janna Simonsen, (BLM).

Regional/Local Setting & Topography

This location is proposed approximately 12 road miles southeast of Myton, Utah just south of the Pleasant Valley Wash and just west of the Duchesne / Uintah County line. The landowner was invited but chose not to attend the pre-site inspection. The surrounding topography varies mostly with rolling hills and small drainages. The site is characterized by greasewood, grasses, brush, and other forbs.

Surface Use Plan

Current Surface Use

Grazing
Wildlife Habitat

New Road

Miles

0.72

Well Pad

Width 154 **Length** 305

Src Const Material

Onsite

Surface Formation

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

greasewood, grasses, forbs.

Soil Type and Characteristics

gravelly clay

Erosion Issues Y

Erosive upon disturbance.

Sedimentation Issues Y

Erosion will cause sediment to be dumped into wet wash adjacent to well pad.

Site Stability Issues Y

Pad should remain stable if drainages are kept away from pad.

Drainage Diversion Required? Y

Divert drainages around and away from the location and access road.

Berm Required? Y

Berm location to prevent leaks and spills from leaving the pad.

Erosion Sedimentation Control Required? Y

Diversions and rip-rap should be used where needed.

Paleo Survey Run? Y Paleo Potential Observed? N Cultural Survey Run? Y Cultural Resources? N

Reserve Pit

Site-Specific Factors		Site Ranking
Distance to Groundwater (feet)	25 to 75	15
Distance to Surface Water (feet)		20
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	>1320	0
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	10 to 20	5
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
Final Score		55 1 Sensitivity Level

Characteristics / Requirements

Dugout earthen (80' x 40' x 8').

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? N

Other Observations / Comments

I requested to move this location to the west some to avoid the drainage concern @ corner #2? Sent email on 11/7/11 to Tim Eaton at Newfield to check with his notes from this pre-site as mine were inadequate to remind me of the exact decision at this location. Waiting for a reply from Tim prior to proceeding.

Tim Eaton responded back via email that we did agree during the pre-site to move this location to the west slightly. We also agreed with the drainage diversions. Newfield needed to re-survey and draw the plats for the move.

Mark Jones
Evaluator

10/11/2011
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
4765	43013510030000	LOCKED	OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	Gerald N. Andersen	
Well Name	Ute Tribal 10-15-4-1W		Unit		
Field	UNDESIGNATED		Type of Work	DRILL	
Location	NWSE 15 4S 1W U 1797 FSL 2162 FEL GPS Coord (UTM) 586831E 4442977N				

Geologic Statement of Basis

The mineral rights for the proposed well are owned by the Ute Tribe. The BLM will be the agency responsible for evaluating and approving the drilling, casing and cement programs.

Brad Hill
APD Evaluator

11/8/2012
Date / Time

Surface Statement of Basis

This location is proposed approximately 12 road miles southeast of Myton, Utah just south of the Pleasant Valley Wash and just west of the Duchesne / Uintah County line. The landowner was invited but chose not to attend the pre-site inspection. The surrounding topography varies mostly with rolling hills and small drainages. The site is characterized by greasewood, grasses, brush, and other forbs. The drianage on the west side of the pad should be diverted around the north side of the pad. The drainage at corner #2 should be diverted enough to keep it well away from the toe of the fill at this corner and side of the pad. The location should be bermed to prevent spills from leaving the confines of the pad. Fencing around the reserve pit will be necessary once the well is drilled to prevent wildlife and livestock from becoming a problem. Drainages should be diverted around and away from wellpad and access road. A synthetic liner of 16 mils (minimum) should be utilized in the reserve pit.

Mark Jones
Onsite Evaluator

10/11/2011
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location. Specifically the drianage on the west should be diverted around the north side of the location. The drianage issue at corner #2 should be re-routed enough to protect this area of the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 10/10/2011

API NO. ASSIGNED: 43013510030000

WELL NAME: Ute Tribal 10-15-4-1W

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: NWSE 15 040S 010W

Permit Tech Review: ☒

SURFACE: 1797 FSL 2162 FEL

Engineering Review: ☐

BOTTOM: 1797 FSL 2162 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.13264

LONGITUDE: -109.98079

UTM SURF EASTINGS: 586831.00

NORTHINGS: 4442977.00

FIELD NAME: UNDESIGNATED

LEASE TYPE: 2 - Indian

LEASE NUMBER: 2OG0005609

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ PLAT
- ☒ Bond: INDIAN - RLB0010462
- ☐ Potash
- ☐ Oil Shale 190-5
- ☐ Oil Shale 190-3
- ☐ Oil Shale 190-13
- ☒ Water Permit: 437478
- ☐ RDCC Review:
- ☒ Fee Surface Agreement
- ☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

- ☐ R649-2-3.
- Unit:
- ☐ R649-3-2. General
- ☐ R649-3-3. Exception
- ☒ Drilling Unit
- Board Cause No: R649-3-2
- Effective Date:
- Siting:
- ☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason
5 - Statement of Basis - bhill
23 - Spacing - dmason

RECEIVED: November 08, 2012



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Ute Tribal 10-15-4-1W

API Well Number: 43013510030000

Lease Number: 2OG0005609

Surface Owner: FEE (PRIVATE)

Approval Date: 11/8/2012

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-2. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Compliance with the Conditions of Approval/Application for Permit to Drill

outlined in the Statement of Basis (copy attached).

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

OCT 11 2011

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010


APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		CONFIDENTIAL	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		2. Name of Operator NEWFIELD PRODUCTION COMPANY Contact: MANDIE CROZIER Email: mcrozier@newfield.com	
3a. Address ROUTE #3 BOX 3630 MYTON, UT 84052		3b. Phone No. (include area code) Ph: 435-646-4825 Fx: 435-646-3031	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWSE 1818FSL 2140FEL At proposed prod. zone NWSE 1818FSL 2140FEL		5. Lease Serial No. 20G0005609	
14. Distance in miles and direction from nearest town or post office* 12.9		6. If Indian, Allottee or Tribe Name	
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1818'		7. If Unit or CA Agreement, Name and No.	
16. No. of Acres in Lease 520.00		8. Lease Name and Well No. UTE TRIBAL 10-15-4-1W	
17. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1168'		9. API Well No. 43-013-S1003	
18. Proposed Depth 7270 MD 7270 TVD		10. Field and Pool, or Exploratory UNDESIGNATED	
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5034 GL		11. Sec., T., R., M., or Blk. and Survey or Area Sec 15 T4S R1W Mer UBM	
22. Approximate date work will start 04/01/2012		12. County or Parish DUCHESNE	
23. Estimated duration 7 DAYS		13. State UT	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) MANDIE CROZIER Ph: 435-646-4825	Date 10/10/2011
Title REGULATORY ANALYST		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date FEB 06 2013
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Electronic Submission #119748 verified by the BLM Well Information System
For NEWFIELD PRODUCTION COMPANY, sent to the Vernal
Committed to AFMSS for processing by LESLIE ROBINSON on 10/12/2011 ()

VOICE OF APPROVAL

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

12SS0889AE

NOS 10/17/2011



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Newfield Production Company
Well No: Ute Tribal 10-15-4-1W
API No: 43-013-51003

Location: NWSE, Sec. 15, T4S, R1E
Lease No: 2OG0005609
Agreement: N/A

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Construction Activity (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig.
Spud Notice (Notify BLM Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm_ut_vn_opreport@blm.gov .
BOP & Related Equipment Tests (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify BLM Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

CONDITIONS OF APPROVAL:

- The drainage in corner 2 will be rerouted in order to flow east thereby preventing hydrologic accumulations and erosional damage.

Paleontological Mitigation:

- It is recommended that the access road for proposed locations 10-15-4-1W and 11-15-4-1W be moved 25 feet to the west to avoid localities of scientifically important fossils and a monitor be present at the time of construction; however since this is private surface, the BLM can't require this.
- After cessation of drilling and completion operations, any visible or measurable layer of oil must be removed from the surface of the reserve pit and the pit kept free of oil.
- Pits must be free of oil and other liquid and solid wastes prior to filling. Pit liners must not be breached (cut) or filled (squeezed) while still containing fluids. The pit liner must be removed to the solids level or treated to prevent its reemergence to the surface or its interference with long-term successful revegetation.
- A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be installed and maintained in the reserve pit.
- Low water crossings will be constructed at drainage crossings as necessary along access road route.
- Any deviation from submitted APD's and ROW applications the operator will notify the BLM in writing and will receive written authorization of any such change with appropriate authorization.
- All operator employees and/or authorized personnel (sub-contractors) in the field will have approved applicable APD's and ROW permits/authorizations on their person(s) during all phases of construction.
- All vehicular traffic, personnel movement, construction/restoration operations shall be confined to the area examined and approved, and to the existing roadways and/or evaluated access routes.
- All permanent surface equipment (meaning on site for six months or longer) will be painted Covert Green to match the surrounding landscape color unless otherwise authorized. This will include all facilities except those required to comply with Occupational Safety and Health Act (OSHA) regulations.
- Reclamation will be completed in accordance with the recontouring and reseeding procedures outlined in the Newfield Exploration Company Castle Peak and Eight Mile Flat Reclamation Plan on file with the Vernal Field Office of the BLM, unless otherwise specified by the private surface owner.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- Newfield Production Co. shall adhere to all referenced requirements in the SOP (version: "Ute Tribe Green River Development Plan", April 17, 2008). The Operator shall also comply with applicable laws and regulations; with lease terms, Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the authorized office.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of

each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.


- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in CD (compact disc) format to the Vernal BLM Field Office. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 20G0005609			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute Tr			
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: UTE TRIBAL 10-15-4-1W			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1797 FSL 2162 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 15 Township: 04.0S Range: 01.0W Meridian: U		9. API NUMBER: 43013510030000			
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: UNDESIGNATED			
COUNTY: DUCHESNE		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/8/2013 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: 			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Newfield proposes to extend the Application for Permit to Drill this well.					
Approved by the Utah Division of Oil, Gas and Mining Date: <u>October 16, 2013</u> By: <u></u>					
NAME (PLEASE PRINT) Mandie Crozier		PHONE NUMBER 435 646-4825			
SIGNATURE N/A		TITLE Regulatory Tech DATE 10/9/2013			



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013510030000

API: 43013510030000

Well Name: UTE TRIBAL 10-15-4-1W

Location: 1797 FSL 2162 FEL QTR NWSE SEC 15 TWNP 040S RNG 010W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/8/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 10/9/2013

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers
GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MARK GARDEN GULCH 1	4620' 4811'
				GARDEN GULCH 2 POINT 3	4944' 5257'
				X MRKR Y MRKR	5465' 5499'
				DOUGLAS CREEK MRK BI CARBONATE MRK	5638' 5983'
				B LIMESTONE MRK CASTLE PEAK	6074' 6478'
				BASAL CARBONATE WASATCH	6875' 7004'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Heather CalderTitle Regulatory Technician

Signature

Heather Calder

Date

06/30/2014

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 15 T4S, R1W
Ute Tribal 10-15-4-1W
Wellbore #1**

Design: Actual

End of Well Report

14 May, 2014





Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION Project: USGS Myton SW (UT) Site: SECTION 15 T4S, R1W Well: Ute Tribal 10-15-4-1W Wellbore: Wellbore #1 Design: Actual		Local Co-ordinate Reference: TVD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329) MD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329) North Reference: True Survey Calculation Method: Minimum Curvature Database: EDM 5000.1 Single User Db	
Project USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		System Datum: Mean Sea Level	
Map System: US State Plane 1983 Geo Datum: North American Datum 1983 Map Zone: Utah Central Zone			
Site SECTION 15 T4S, R1W			
Site Position: From: Map Position Uncertainty: 0.0 usft		Northings: 7,221,618.19 usft Eastings: 2,064,643.83 usft Slot Radius: 13-3/16 "	
		Latitude: 40° 8' 7.199 N Longitude: 109° 58' 57.286 W Grid Convergence: 0.97 °	
Well Ute Tribal 10-15-4-1W, SHL: 40° 7' 57.790 -109° 58' 50.960			
Well Position +N/-S 0.0 usft +E/-W 0.0 usft Position Uncertainty 0.0 usft		Northings: 7,220,674.66 usft Eastings: 2,065,151.26 usft Wellhead Elevation: 5,047.0 usft	
		Latitude: 40° 7' 57.790 N Longitude: 109° 58' 50.960 W Ground Level: 5,034.0 usft	
Wellbore Wellbore #1			
Magnetics		Model Name IGRF2010 Sample Date 4/24/2014 Declination (°) 10.93 Dip Angle (°) 65.81 Field Strength (nT) 52,051	
Design Actual			
Audit Notes:			
Version: 1.0 Phase: ACTUAL Tie On Depth: 0.0		Depth From (TVD) (usft) 0.0 +N/-S (usft) 0.0 +E/-W (usft) 0.0 Direction (°) 47.79	
Survey Program		Date 5/14/2014	
From (usft) 586.0 To (usft) 7,228.0 Survey (Wellbore) Survey #1 (Wellbore #1)		Tool Name MWD Description MWD - Standard	



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 15 T4S, R1W
Well: Ute Tribal 10-15-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Ute Tribal 10-15-4-1W
TVD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
MD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
	586.0	0.60	271.00	586.0	-2.2	0.1	-3.1	0.10	0.10	0.00
	616.0	0.70	253.20	616.0	-2.5	0.0	-3.4	0.75	0.33	-59.33
	648.0	0.40	302.60	648.0	-2.7	0.0	-3.7	1.67	-0.94	154.37
	679.0	1.00	27.00	679.0	-2.5	0.3	-3.6	3.36	1.94	272.26
	710.0	2.00	45.40	710.0	-1.7	0.9	-3.1	3.54	3.23	59.35
	741.0	3.10	52.80	740.9	-0.3	1.8	-2.1	3.70	3.55	23.87
	771.0	4.00	52.70	770.9	1.5	2.9	-0.6	3.00	3.00	-0.33
	802.0	4.50	53.20	801.8	3.8	4.3	1.2	1.62	1.61	1.61
	832.0	4.40	53.10	831.7	6.1	5.7	3.1	0.33	-0.33	-0.33
	862.0	4.70	50.40	861.6	8.5	7.2	5.0	1.23	1.00	-9.00
	893.0	4.60	53.00	892.5	11.0	8.8	6.9	0.75	-0.32	8.39
	936.0	4.40	53.70	935.4	14.4	10.8	9.6	0.48	-0.47	1.63
	980.0	4.40	56.20	979.2	17.7	12.7	12.4	0.44	0.00	5.68
	1,023.0	4.50	56.90	1,022.1	21.0	14.5	15.2	0.26	0.23	1.63
	1,067.0	4.50	57.10	1,066.0	24.4	16.4	18.1	0.04	0.00	0.45
	1,110.0	4.60	55.60	1,108.8	27.8	18.3	20.9	0.36	0.23	-3.49
	1,154.0	4.40	54.70	1,152.7	31.2	20.3	23.7	0.48	-0.45	-2.05
	1,198.0	4.30	53.80	1,196.6	34.5	22.2	26.5	0.28	-0.23	-2.05
	1,241.0	4.30	55.80	1,239.5	37.7	24.1	29.1	0.35	0.00	4.65
	1,284.0	4.30	58.00	1,282.3	40.9	25.9	31.8	0.38	0.00	5.12
	1,327.0	4.00	57.30	1,325.2	44.0	27.5	34.4	0.71	-0.70	-1.63
	1,370.0	3.80	56.40	1,368.1	46.9	29.1	36.9	0.49	-0.47	-2.09
	1,413.0	3.80	55.20	1,411.0	49.7	30.7	39.2	0.18	0.00	-2.79
	1,456.0	3.80	58.30	1,453.9	52.5	32.3	41.6	0.48	0.00	7.21
	1,500.0	3.70	60.00	1,497.8	55.3	33.8	44.1	0.34	-0.23	3.86
	1,543.0	3.60	59.20	1,540.8	58.0	35.1	46.4	0.26	-0.23	-1.86



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Mylon SW (UT)
Site: SECTION 15 T4S, R1W
Well: Ute Tribal 10-15-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Ute Tribal 10-15-4-1W
TVD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
MD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	1,587.0		3.60	56.90	1,584.7	60.7	36.6	48.8	0.33	0.00
	1,631.0		4.00	54.60	1,628.6	63.6	38.2	51.2	0.97	0.91
	1,675.0		4.10	53.20	1,672.5	66.7	40.1	53.7	0.32	0.23
	1,718.0		4.10	54.30	1,715.4	69.8	41.9	56.2	0.18	0.00
	1,762.0		4.10	54.20	1,759.2	72.9	43.7	58.7	0.02	0.00
	1,806.0		4.00	55.00	1,803.1	76.0	45.5	61.3	0.26	-0.23
	1,848.0		4.00	56.80	1,845.0	78.9	47.2	63.7	0.30	0.00
	1,891.0		3.90	57.30	1,887.9	81.8	48.8	66.2	0.25	-0.23
	1,935.0		3.90	55.60	1,931.8	84.8	50.4	68.7	0.26	0.00
	1,979.0		3.80	52.10	1,975.7	87.7	52.2	71.1	0.58	-0.23
	2,022.0		4.50	41.80	2,018.6	90.8	54.3	73.3	2.37	1.63
	2,066.0		4.60	39.10	2,062.5	94.2	57.0	75.6	0.54	0.23
	2,110.0		4.60	38.50	2,106.3	97.7	59.7	77.8	0.11	0.00
	2,154.0		4.50	38.90	2,150.2	101.2	62.4	80.0	0.24	-0.23
	2,198.0		4.40	39.90	2,194.1	104.6	65.1	82.1	0.29	-0.23
	2,241.0		4.00	39.70	2,237.0	107.7	67.5	84.1	0.93	-0.93
	2,285.0		3.50	37.90	2,280.9	110.5	69.7	85.9	1.17	-1.14
	2,328.0		3.20	36.30	2,323.8	113.0	71.7	87.5	0.73	-0.70
	2,372.0		2.90	35.30	2,367.7	115.3	73.6	88.8	0.69	-0.68
	2,416.0		2.60	37.60	2,411.7	117.3	75.3	90.1	0.73	-0.68
	2,460.0		3.40	39.10	2,455.6	119.6	77.1	91.5	1.83	1.82
	2,502.0		3.30	42.10	2,497.5	122.1	79.0	93.1	0.48	-0.24
	2,546.0		2.90	43.80	2,541.5	124.4	80.8	94.7	0.93	-0.91
	2,590.0		3.50	42.70	2,585.4	126.9	82.5	96.4	1.37	1.36
	2,634.0		3.10	43.40	2,629.3	129.4	84.4	98.1	0.91	-0.91
	2,678.0		3.90	43.20	2,673.2	132.1	86.3	100.0	1.82	1.82
	2,720.0		3.70	43.00	2,715.2	134.8	88.4	101.9	0.48	-0.48



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Mylon SW (UT)
Site: SECTION 15 T4S, R1W
Well: Ute Tribal 10-15-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Ute Tribal 10-15-4-1W
TVD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
MD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey											
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)		
2,764.0	3.30	45.30	2,759.1	137.5	90.3	103.8	0.96	-0.91	5.23		
2,808.0	2.80	50.10	2,803.0	139.9	91.9	105.5	1.28	-1.14	10.91		
2,852.0	3.50	40.70	2,846.9	142.3	93.6	107.2	1.97	1.59	-21.36		
2,894.0	3.30	39.10	2,888.9	144.7	95.5	108.8	0.53	-0.48	-3.81		
2,938.0	4.20	41.60	2,932.8	147.6	97.7	110.6	2.08	2.05	5.68		
2,982.0	4.00	42.00	2,976.7	150.7	100.0	112.7	0.46	-0.45	0.91		
3,025.0	3.50	41.50	3,019.6	153.5	102.1	114.6	1.17	-1.16	-1.16		
3,067.0	3.00	38.40	3,061.5	155.9	104.0	116.1	1.26	-1.19	-7.38		
3,111.0	3.40	34.80	3,105.4	158.3	105.9	117.6	1.02	0.91	-8.18		
3,155.0	3.10	31.40	3,149.4	160.7	108.0	119.0	0.81	-0.68	-7.73		
3,199.0	3.70	30.60	3,193.3	163.2	110.3	120.3	1.37	1.36	-1.82		
3,243.0	3.50	28.90	3,237.2	165.8	112.7	121.7	0.52	-0.45	-3.86		
3,286.0	4.40	36.00	3,280.1	168.7	115.1	123.3	2.38	2.09	16.51		
3,330.0	4.30	38.90	3,324.0	172.0	117.8	125.3	0.55	-0.23	6.59		
3,373.0	4.50	39.80	3,366.8	175.2	120.3	127.4	0.49	0.47	2.09		
3,417.0	4.50	39.70	3,410.7	178.6	123.0	129.6	0.02	0.00	-0.23		
3,461.0	4.00	39.50	3,454.6	181.9	125.5	131.7	1.14	-1.14	-0.45		
3,548.0	3.40	37.40	3,541.4	187.4	129.9	135.2	0.71	-0.69	-2.41		
3,592.0	2.70	32.40	3,585.3	189.7	131.8	136.5	1.70	-1.59	-11.36		
3,635.0	2.90	23.50	3,628.3	191.7	133.7	137.5	1.11	0.47	-20.70		
3,679.0	2.30	16.10	3,672.2	193.4	135.5	138.2	1.56	-1.36	-16.82		
3,722.0	3.10	15.40	3,715.2	195.1	137.5	138.8	1.86	1.86	-1.63		
3,765.0	2.70	10.20	3,758.1	196.9	139.6	139.2	1.11	-0.93	-12.09		
3,807.0	2.10	8.70	3,800.1	198.3	141.3	139.5	1.44	-1.43	-3.57		
3,851.0	1.60	3.20	3,844.1	199.4	142.7	139.7	1.20	-1.14	-12.50		
3,894.0	2.20	18.80	3,887.1	200.5	144.1	140.0	1.83	1.40	36.28		
3,938.0	3.30	28.50	3,931.0	202.5	146.0	140.9	2.71	2.50	22.05		



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 15 T4S, R1W
Well: Ute Tribal 10-15-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
 Well Ute Tribal 10-15-4-1W
 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
TVD Reference:
 True
North Reference:
 Minimum Curvature
Survey Calculation Method:
 EDM 5000.1 Single User Db
Database:

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	3,982.0	4.10	32.80	3,974.9	205.2	148.5	142.3	1.92	1.82	9.77
	4,025.0	3.10	30.80	4,017.8	207.8	150.8	143.8	2.34	-2.33	-4.65
	4,068.0	2.20	29.30	4,060.8	209.7	152.5	144.8	2.10	-2.09	-3.49
	4,112.0	1.70	21.40	4,104.8	211.0	153.8	145.4	1.29	-1.14	-17.95
	4,155.0	1.20	11.10	4,147.7	212.0	154.9	145.7	1.31	-1.16	-23.95
	4,198.0	1.90	13.00	4,190.7	212.9	156.0	146.0	1.63	1.63	4.42
	4,242.0	2.50	18.00	4,234.7	214.4	157.6	146.4	1.43	1.36	11.36
	4,286.0	3.00	21.40	4,278.6	216.2	159.6	147.1	1.19	1.14	7.73
	4,329.0	3.00	22.10	4,321.6	218.2	161.7	148.0	0.09	0.00	1.63
	4,373.0	2.40	18.30	4,365.5	220.1	163.6	148.7	1.42	-1.36	-8.64
	4,415.0	1.80	10.10	4,407.5	221.4	165.1	149.1	1.59	-1.43	-19.52
	4,458.0	1.30	5.00	4,450.5	222.3	166.3	149.3	1.21	-1.16	-11.86
	4,502.0	1.00	359.60	4,494.5	222.9	167.2	149.3	0.72	-0.68	-12.27
	4,546.0	0.40	321.10	4,538.5	223.1	167.7	149.2	1.66	-1.36	-87.50
	4,589.0	0.50	264.60	4,581.5	223.0	167.8	148.9	1.01	0.23	-131.40
	4,633.0	0.80	240.50	4,625.5	222.6	167.6	148.5	0.91	0.68	-54.77
	4,677.0	1.20	234.30	4,669.5	221.8	167.2	147.8	0.94	0.91	-14.09
	4,721.0	1.40	235.20	4,713.5	220.8	166.6	147.0	0.46	0.45	2.05
	4,764.0	1.60	227.80	4,756.4	219.7	165.9	146.1	0.65	0.47	-17.21
	4,808.0	1.90	220.80	4,800.4	218.3	164.9	145.2	0.84	0.68	-15.91
	4,851.0	1.90	215.40	4,843.4	216.9	163.8	144.3	0.42	0.00	-12.56
	4,894.0	2.00	214.30	4,886.4	215.5	162.6	143.5	0.25	0.23	-2.56
	4,937.0	2.20	216.50	4,929.3	214.0	161.3	142.6	0.50	0.47	5.12
	4,981.0	2.30	217.00	4,973.3	212.3	159.9	141.5	0.23	0.23	1.14
	5,025.0	2.40	215.50	5,017.3	210.5	158.5	140.5	0.27	0.23	-3.41
	5,068.0	2.60	212.40	5,060.2	208.7	156.9	139.4	0.56	0.47	-7.21
	5,112.0	2.60	210.90	5,104.2	206.8	155.2	138.4	0.15	0.00	-3.41



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 15 T4S, R1W
Well: Ute Tribal 10-15-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Ute Tribal 10-15-4-1W
TVD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
MD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
5,156.0	2.70	210.40	5,148.1	204.8	153.5	137.3	0.23	0.23	-1.14
5,200.0	2.80	213.40	5,192.1	202.8	151.7	136.2	0.40	0.23	6.82
5,244.0	3.00	208.90	5,236.0	200.7	149.8	135.1	0.69	0.45	-10.23
5,287.0	3.20	206.50	5,279.0	198.5	147.7	134.0	0.55	0.47	-5.58
5,331.0	3.30	203.90	5,322.9	196.2	145.5	132.9	0.40	0.23	-5.91
5,375.0	3.40	204.20	5,366.8	193.8	143.1	131.9	0.23	0.23	0.68
5,418.0	3.30	204.20	5,409.8	191.5	140.8	130.9	0.23	-0.23	0.00
5,462.0	3.40	204.30	5,453.7	189.2	138.5	129.8	0.23	0.23	0.23
5,505.0	3.40	204.20	5,496.6	186.8	136.2	128.8	0.01	0.00	-0.23
5,549.0	3.60	204.50	5,540.5	184.4	133.7	127.6	0.46	0.45	0.68
5,592.0	3.80	204.70	5,583.4	181.8	131.2	126.5	0.47	0.47	0.47
5,635.0	3.80	205.60	5,626.3	179.2	128.6	125.3	0.14	0.00	2.09
5,679.0	3.10	216.90	5,670.3	176.7	126.3	123.9	2.21	-1.59	25.68
5,723.0	1.90	232.10	5,714.2	174.8	124.9	122.6	3.09	-2.73	34.55
5,767.0	2.10	235.90	5,758.2	173.3	124.0	121.4	0.55	0.45	8.64
5,810.0	1.50	241.50	5,801.2	171.9	123.3	120.3	1.45	-1.40	13.02
5,896.0	2.20	237.80	5,887.1	169.2	121.9	117.9	0.83	0.81	-4.30
5,940.0	2.70	236.60	5,931.1	167.3	120.9	116.3	1.14	1.14	-2.73
5,983.0	2.90	240.50	5,974.0	165.3	119.8	114.5	0.64	0.47	9.07
6,027.0	3.40	240.40	6,018.0	162.9	118.6	112.4	1.14	1.14	-0.23
6,071.0	3.90	241.10	6,061.9	160.2	117.2	109.9	1.14	1.14	1.59
6,115.0	3.80	238.60	6,105.8	157.3	115.8	107.4	0.44	-0.23	-5.68
6,157.0	3.90	237.00	6,147.7	154.5	114.2	105.0	0.35	0.24	-3.81
6,200.0	3.90	233.80	6,190.6	151.6	112.6	102.6	0.51	0.00	-7.44
6,243.0	3.70	234.80	6,233.5	148.8	110.9	100.3	0.49	-0.47	2.33
6,285.0	3.30	232.60	6,275.4	146.3	109.4	98.2	1.00	-0.95	-5.24
6,329.0	3.00	232.90	6,319.3	143.8	107.9	96.3	0.68	-0.68	0.68



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 15 T4S, R1W
Well: Ute Tribal 10-15-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
MD Reference: 10-15-4-1W @ 5047.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	6,373.0	3.00	233.30	6,363.3	141.6	106.6	94.5	0.05	0.00	0.91
	6,417.0	3.10	240.70	6,407.2	139.2	105.3	92.5	0.92	0.23	16.82
	6,461.0	3.00	238.90	6,451.2	137.0	104.1	90.5	0.31	-0.23	-4.09
	6,500.0	3.00	231.10	6,490.1	134.9	102.9	88.8	1.05	0.00	-20.00
	6,548.0	3.00	227.60	6,538.0	132.4	101.3	86.9	0.38	0.00	-7.29
	6,592.0	2.90	227.10	6,582.0	130.2	99.8	85.2	0.23	-0.23	-1.14
	6,636.0	2.80	225.10	6,625.9	128.0	98.3	83.7	0.32	-0.23	-4.55
	6,679.0	2.80	219.20	6,668.9	125.9	96.7	82.2	0.67	0.00	-13.72
	6,722.0	2.90	210.70	6,711.8	123.8	95.0	81.0	1.01	0.23	-19.77
	6,766.0	2.80	205.90	6,755.8	121.7	93.0	80.0	0.59	-0.23	-10.91
	6,809.0	2.70	199.70	6,798.7	119.9	91.1	79.2	0.73	-0.23	-14.42
	6,853.0	2.70	194.10	6,842.7	118.1	89.2	78.6	0.60	0.00	-12.73
	6,897.0	2.80	194.70	6,886.6	116.3	87.1	78.1	0.24	0.23	1.36
	6,941.0	2.70	192.80	6,930.6	114.6	85.1	77.6	0.31	-0.23	-4.32
	6,984.0	2.80	189.90	6,973.5	112.9	83.0	77.2	0.40	0.23	-6.74
	7,028.0	2.90	184.40	7,017.5	111.3	80.9	76.9	0.66	0.23	-12.50
	7,072.0	3.00	180.80	7,061.4	109.7	78.6	76.8	0.48	0.23	-8.18
	7,116.0	3.00	176.70	7,105.3	108.2	76.3	76.8	0.49	0.00	-9.32
	7,159.0	3.10	173.20	7,148.3	106.8	74.0	77.0	0.49	0.23	-8.14
	7,168.0	3.10	172.90	7,157.3	106.5	73.5	77.1	0.18	0.00	-3.33
	7,228.0	3.10	170.90	7,217.2	104.7	70.3	77.6	0.18	0.00	-3.33

Checked By: _____




Approved By: _____

Date: _____



Project: USGS Myton SW (UT)
Site: SECTION 15 T4S, R1W
Well: Ute Tribal 10-15-4-1W
Wellbore: Wellbore #1
Design: Actual

Azimuths to True North
Magnetic North: 10.93°
Magnetic Field
Strength: 52050.8nT
Dip Angle: 65.81°
Date: 4/24/2014
Model: IGRF2010



Design: Actual (Ute Tribal 10-15-4-1W/Wellbore #1)

Created By: *Matthew London* Date: 12:52, May 14 2014

THIS SURVEY IS CORRECT TO THE BEST OF
MY KNOWLEDGE AND IS SUPPORTED
BY ACTUAL FIELD DATA

Well Name: Ute Tribal 10-15-4-1W

Job Category	Job Start Date	Job End Date

Daily Operations			
Report Start Date	Report End Date	24hr Activity Summary	
5/29/2014	5/30/2014	Ran CBL & Perf Stage # 1.	
Start Time	07:00	End Time	07:00
Start Time	07:00	End Time	10:00
Start Time	10:00	End Time	13:00
Start Time	13:00	End Time	14:00
Start Time	14:00	End Time	00:00
Report Start Date	Report End Date	24hr Activity Summary	
5/31/2014	6/1/2014	Frac stgs. 1-5	
Start Time	00:00	End Time	10:00
Start Time	10:00	End Time	11:00
Start Time	11:00	End Time	12:30
Start Time	12:30	End Time	13:45
Start Time	13:45	End Time	14:30
Start Time	14:30	End Time	15:30
Start Time	15:30	End Time	16:15
Start Time	16:15	End Time	17:00



Summary Rig Activity

Start Time	17:00	End Time	17:30	Comment
Start Time	17:30	End Time	18:15	R/U W/L Pres. test lub to 4000# (good) RIH @ 320' pm set CFP @ 6030' and perf stg. # 4, C- sands, D3 f/ (5952-56')(5916-18')(5866-68')(5852-54') 2 spf @ 180 deg. Phasing POOH L/D setting tool and guns Turn over to Nabors
Start Time	18:15	End Time	19:00	Comment
Start Time	19:00	End Time	19:30	Frac Stg 4, (C-Sand & D3), w/ 162,003 of 20/40 in 1241 total bbls fluid. Open pressure 1743 psi. Broke @ 1843 psi @ 3.2 BPM w/ .7 bbls. F/ inj rate 32 bpm @ 2505, ISIP @ 1442 for FG of .69. Treated w/ ave pressure of 2326 psi & ave rate of 42.5 BPM. Max treating pressure 2996 psi & max rate of 43.1 BPM, ISIP 2454 psi, FG: .86, Extreme W/L
Start Time	19:30	End Time	00:00	Comment
Start Time	19:30	End Time	00:00	R/U W/L Pres. test lub to 4000# (good) RIH @ 320' pm set CFP @ 5740' and perf stg. # 4, D1 f/ (5660-64') 3 spf @ 120 deg. Phasing POOH L/D setting tool and guns Turn over to Nabors
Start Time	19:30	End Time	00:00	Comment
Start Time	19:30	End Time	00:00	Frac Stg 5, (D1), w/ 210,686 of 20/40 in 1342 total bbls fluid. Open pressure 1487 psi. Broke @ 1579 psi @ 1.8 BPM w/ 1.2 bbls. F/ inj rate 21 bpm @ 2479, ISIP @ 1482 for FG of .70. Treated w/ ave pressure of 2396 psi & ave rate of 24.8 BPM. Max treating pressure 2805 psi & max rate of 25.9 BPM, ISIP 2102 psi, FG: .82, Extreme W/L
Start Time	19:30	End Time	00:00	Comment
Start Time	19:30	End Time	00:00	Attempt to open well to flow back and the weld f/ 2-1/16 valves off the single blind to flowback iron had cracked so we had to wait on replacement iron
Report Start Date	6/1/2014	Report End Date	6/2/2014	24hr Activity Summary
Start Time	00:00	End Time	02:00	Flow well back at 3 bpm, run 2-KP's
Start Time	02:00	End Time	06:00	Comment
Start Time	06:00	End Time	12:00	Cont. to replace flange off BOPE to begin flow back
Start Time	12:00	End Time	16:00	Open well to flow back @ 3 bpm recovered ~720 bbls and well slowly died (no signs of oil) SWI
Start Time	16:00	End Time	18:00	Decided to bring in a H/O and attempt to flush csg. if poss. to top perf, wait on H/O truck
Start Time	18:00	End Time	00:00	Comment
Start Time	18:00	End Time	00:00	MIRU Preferred H/O hold PJSM, R/U and pump 20 bbls and pres. increased to 2400# 1.5 bpm and broke free pumped add. 120 bbls @ 1.5 bpm and 800# flushed to top perf
Start Time	18:00	End Time	00:00	Comment
Start Time	18:00	End Time	00:00	MIRU Extreme W/L RIH set 5-1/2 CBP @ 5530' POOH w/ setting tool, preform 30 min. test (good) RIH and set 2nd plug @ 5520' POOH R/D W/L
Start Time	18:00	End Time	00:00	Comment
Start Time	18:00	End Time	00:00	SDFN
Report Start Date	6/2/2014	Report End Date	6/3/2014	24hr Activity Summary
Start Time	00:00	End Time	05:30	P/U RIH w/ POBS w/ float and X nipple tag KP @5520' R/U RBS pwr swl SWI
Start Time	05:30	End Time	07:00	Comment
Start Time	07:00	End Time	07:45	SDFN
Start Time	07:45	End Time	08:45	Comment
Start Time	08:45	End Time	10:45	Crew Travel
Start Time	10:45	End Time	11:15	Comment
Start Time	10:45	End Time	11:15	PRE TRIP INSPECTIONS, DOT PAPERWORK, MOVE RIG FROM THE UTE TRIBAL 8-23-4-1W.
Start Time	10:45	End Time	11:15	Comment
Start Time	10:45	End Time	11:15	SPOT IN RIG UP DERRICK INSPECTION
Start Time	10:45	End Time	11:15	Comment
Start Time	10:45	End Time	11:15	NIPPLE DOWN 10K FRAC STACK & CAMERON 10K SLEEVE, NIPPLE UP 5K KNIGHT DRILL OUT STACK
Start Time	10:45	End Time	11:15	Comment
Start Time	10:45	End Time	11:15	RIG UP WORK FLOOR, TONGS, PICK UP LINE ETC

NEWFIELD**Well Name: Ute Tribal 10-15-4-1W****Summary Rig Activity**

Start Time	11:15	End Time	14:00
		Comment	R/U RBS PRESSURE TEST ALL COMPONENTS OF BOPE AS PER NEWFIELD REG., GATE VALVES, PREP AND TALLY TUBING, RIG UP PUMP LINES.
Start Time	14:00	End Time	18:30
		Comment	PICK UP AND MAKE UP BHA OF CONCAVE 4.750" MILL, POP OFF BIT SUB, 1 JOINT OF 2 7/8" TUBING AND A X NIPPLE, PICK UP TUBING, TALLY TUBING AS WE GO.
Start Time	18:30	End Time	19:30
		Comment	RIG UP RBS PWR SWVL. TIE UP HOSES PICK UP FIRST JOINT SWI
Start Time	19:30	End Time	20:30
		Comment	Crew Travel
Start Time	20:30	End Time	00:00
		Comment	SDFN
Report Start Date	6/3/2014	Report End Date	6/4/2014
24hr Activity Summary			
D/O all CBP's C/O to PBTD @ 7118' start ooh w/ D/O BHA EOT @ 5050' SWI			
Start Time	00:00	End Time	05:30
		Comment	SDFN
Start Time	05:30	End Time	07:00
		Comment	Crew Travel
Start Time	07:00	End Time	07:15
		Comment	CHECK PRESSURES O- ON CSG, 0-ON TUBING OPEN WELL UP
Start Time	07:15	End Time	07:45
		Comment	BREAK CIRC. USED 35 BBLs TO FILL TUBING
Start Time	07:45	End Time	13:45
		Comment	TAG UP ON KILL PLUG # 1 AGAIN @ 5.531', MILL TIME OF 12 MINUTES. TAG KILL PLUG # 2 @ 5.540' MILL TIME OF 17 MINUTES. PICK UP TUBING TAG #3 PLUG @ 5.741', 8' OF SAND ON TOP. MILL TIME OF 15 MINUTES. TAG PLUG PARTS @ 5.917' TAG PLUG 4 @ 6.011' 10' OF FILL, MILL TIME OF 22 MINUTES. MAKE 2 CONNECTIONS ITH SWIVEL AND PICK RACK OUT SWIVEL PICK UP TUBING TO 6.576' TAGGED SAND AND PLUG CONE 104' OF FILL ON TOP OF PLUG. TAGGED PLUG @ 6.680' MILL TIME OF 20 MINUTES. MAKE CONNECTIONS TO PLUG 6 @ 6.911' NO FILL ON PLUG, MILL TIME 20 MINUTES. PICK UP CONNECTIONS TO TAG SAND TOP @ 7.093' 25' OF FILL SWIVEL IN TO PBTD @ 7,118
Start Time	13:45	End Time	14:30
		Comment	CIRC. 170 BBLs TO CLEAN UP BOTTOMS UP. @ 4 BARRELS PER MINUTE
Start Time	14:30	End Time	15:30
		Comment	PULLED OUT OF HOLE WITH 1 JOINT OF TUBING AND STARTED TO OVER PULL WORK PIPE FOR 5 MINUTES AND RIG UP SWIVEL START CIRCULATING. CIRC. 45 BBLs TUBING WAS PULLING FREE LAYED DOWN 3 JOINTS WITH SWIVEL THEN RACKED OUT POWER SWIVEL
Start Time	15:30	End Time	16:30
		Comment	RESUME PULLING OUT OF HOLE WITH TUBING MADE UP BHA INTO STANDS ON THE WAY OUT. PULL OUT OF HOLE WITH 60 JOINTS OF TUBING AND SHUT WELL IN FOR NIGHT FOR NCPS SAFETY MEETING EOT @ 5050'
Start Time	16:30	End Time	18:00
		Comment	Crew Travel
Start Time	18:00	End Time	00:00
		Comment	SDFN
Report Start Date	6/4/2014	Report End Date	6/5/2014
24hr Activity Summary			
Cont. ooh L/D d/o BHA, P/U RIH w/ De-sander prod. BHA, unable to set TAC, start of to replace anchor			
Start Time	00:00	End Time	05:30
		Comment	SDFN



Well Name: Ute Tribal 10-15-4-1W

Summary Rig Activity

Sundry Number: 52923 API Well Number: 43013510030000

Start Time	05:30	End Time	07:00	Comment
Start Time	07:00	End Time	07:30	Crew Travel
Start Time	07:30	End Time	08:45	TUBING PRESSURE WAS 0 PSI, CASING PRESSURE WAS 400 PSI. TRIED TO BLEED DOWN CASING BUT COULD NOT BLEED OFF
Start Time	08:45	End Time	10:00	RIG UP TO CIRC. AND ROLL 100 BBLs OF 4% KCL DOWN TUBING TO KILL WELL.
Start Time	10:00	End Time	12:00	RESUME PULLING OUT OF HOLE WITH TUBING TO PICK UP PROD. BHA.
Start Time	12:00	End Time	13:30	MAKE UP BHA RUN IN HOLE WITH PRODUCTION LAND PSN @ 6,876', SET TUBING ANCHOR WITH 18K TENSION @ 6,842'.
Start Time	13:30	End Time	16:00	UNLANDED WELL TO BREAK OUT 4' PUP JOINT AND THE ANCHOR HAD SLIPPED WOULD NOT PULL OVER BUT THE TUBING WOULD STACK OUT IF WE CAME DOWN, TRIED TO WORK TUBING TO GET ANCHOR SET CORRECTLY THE WELL
Start Time	16:00	End Time	17:30	STARTED TO FLOW OIL WE BROKE OUT 4' PUP AND LANDED WELL. LEAVE WELL LANDED AND CIRC. TO TRY AND KILL WELL AGAIN
Start Time	17:30	End Time	19:00	TO WORK WITH TUBING ANCHOR. CIRC. 150 BBLs DOWN TUBING.
Start Time	19:00	End Time	00:00	WORK WITH TUBING TRYING TO GET ANCHOR TO SET COULD NOT GET IT TO SET WORKED TORQUE TRIED TO PULL A JOINT STILL COULD NOT SET, DECIDED TO PULL TUBING
Start Time	00:00	End Time	05:30	UNLAND WELL START PULLING OUT OF HOLE WITH TUBING. PULLED 60 JOINTS, EOT @ 5,000 SECURE WELL FOR NIGHT
Start Time	05:30	End Time	07:00	Crew travel
Start Time	07:00	End Time	08:15	SDFN
Start Time	08:15	End Time	09:45	Crew Travel
Start Time	09:45	End Time	11:45	CHECK PRESSURES TUBING 250 PSI, CASING 400 PSI. RIG UP PUMP TO CIRC. WHILE BLEEDING WELL OFF. PUMPED 100 BBLs DOWN TUBING. LET WELL EQUALIZE
Start Time	11:45	End Time	13:30	RESUME PULLING OUT OF HOLE WITH TUBING TO THE TAC. UPON INSPECTION OF ANCHOR THE PIPE PLUG WAS MISSING AND BOTTOM CONE MANDREL HAD DROPPED TO THE CAUSING CONE TO BE UNABLE TO ENGAGE SLIPS
Start Time	13:30	End Time	15:00	MAKE UP AND FUNCTION TEST NEW ANCHOR AND RUN IN HOLE WITH TUBING OUT OF DERRICK WELL
Start Time	15:00	End Time	16:30	STARTED TO FLOW UP CASING ON THE TRIP IN INSTALLED A WASHINGTON RUBBER AND RESUMED IN HOLE. STRIP OFF WASHINGTON RUBBER AND STRIP IN LANDING DONUT
Start Time	16:30	End Time	18:00	WITH 4' PUP JOINT UNDER SET TUBING ANCHOR @ 6,842' WITH 18K TENSION
Start Time	18:00	End Time	19:30	RIG DOWN WORK FLOOR N/D 5K D/O STACK. PUMP 15 BBLs DOWN BOTH SIDES AND UNLAND WELL
Start Time	19:30	End Time	21:00	REMOVE 4' PUP JOINT AND LAND WELL FOR PRODUCTION, N/U PROD WELLHEAD

NEWFIELD



Well Name: Ute Tribal 10-15-4-1W

Summary Rig Activity

Start Time	13:30	End Time	14:00	Comment PICK UP TOOLS AND TRIPPING HAZARDS FROM AROUND WELL HEAD AND CHANGE OVER TO ROD EQUIPMENT
Start Time	14:00	End Time	14:30	Comment MOVE TRAILERS AROUND AND SPOT IN ROD TRAILER GET A GOOD ROD COUNT
Start Time	14:30	End Time	18:15	Comment PICK UP NEW JOHN CRANE ROD PUMP AND PICK UP ROD STRING ACCORDING TO ENGINEER SPREAD SHEET FINAL ROD DETAIL IN THE ROD AND TUBING DETAIL
Start Time	18:15	End Time	18:45	Comment SPACE OUT WELL FILL TUBING WITH 2 BBLs AND STROKE TEST PUMP TO 800 PSI. (good)
Start Time	18:45	End Time	19:30	Comment ROLL UNIT HANG HORSE HEAD AND HANG RODS OFF BRIDAL
Start Time	19:30	End Time	21:30	Comment RDSU STACK ON THE SIDE OF LOC. LOAD EQUIPMENT AND FINISH RACKING OUT HARD LINE
Start Time	21:30	End Time	23:00	Comment Crew Travel
Report Start Date	Report End Date	24hr Activity Summary		
6/6/2014	6/7/2014			
Start Time	End Time		Comment	